APPENDIX E

SURVEY DATA

Appendix E

Survey Data
GSA Warehouse Area
Parcels 151(7), 2(7), 3(7), 4(7), 67(7), 69(7), 91(7), 111(7), 128(7), 129(7), and 238(7)
Fort McClellan, Calhoun County, Alabama

Sample Location	Northing	Easting	Ground Elevation (ft msl)	Top of Casing Elevation (ft msl)
FTA-151-DEP01	1171284.05	668651.65	732.01	NA
FTA-151-DEP02	1171109.94	668917.20	733.79	NA
FTA-151-DEP03	1170821.24	669411.15	737.27	NA
FTA-151-DEP04	1170112.85	668876.46	743.50	NA
FTA-151-DEP05	1170311.28	668886.75	743.06	NA
FTA-151-GP01	1171478.07	668145.24	732.25	733.71
FTA-151-GP02	1171552.16	668164.16	730.95	NA
FTA-151-GP03	1171457.89	668317.06	731.87	732.18
FTA-151-GP04	1171365.76	668455.26	731.82	NA
FTA-151-GP05	1171313.29	668454.25	733.34	733.38
FTA-151-GP06	1171280.30	668413.59	732.68	NA
FTA-151-GP08	1171162.10	668599.16	736.02	NA
FTA-151-GP09	1171292.20	668573.52	732.02	NA
FTA-151-GP10	1171227.59	668673.35	732.87	NA
FTA-151-GP11	1171156.37	668687.53	736.23	738.24
FTA-151-GP12	1171139.53	668649.32	736.95	NA
FTA-151-GP13	1171025.26	668787.08	739.52	NA
FTA-151-GP14	1171055.39	668742.88	739.30	NA
FTA-151-GP15	1170996.25	668839.21	739.52	NA
FTA-151-GP16	1171159.16	668754.06	732.24	NA
FTA-151-GP17	1171101.46	668830.03	732.47	NA
FTA-151-GP18	1171007.50	668975.96	734.71	NA
FTA-151-GP19	1170922.79	669091.27	734.41	NA
FTA-151-GP20	1170903.99	668984.72	742.21	NA
FTA-151-GP21	1170870.77	669069.08	733.40	NA
FTA-151-GP22	1170972.02	668942.96	737.47	NA
FTA-151-GP23	1170808.01	669269.30	734.01	NA
FTA-151-GP24	1170739.58	669366.11	736.69	NA
FTA-151-GP25	1170765.18	669197.13	744.47	746.58
FTA-151-GP26	1170690.03	669309.42	746.23	NA
FTA-151-GP27	1170616.55	669434.04	748.22	NA
FTA-151-GP28	1170554.74	669529.35	748.57	NA
FTA-151-GP29	1170620.13	669567.69	739.79	NA
FTA-151-GP30	1170701.00	669436.31	737.77	NA
FTA-151-GP31(W)	1170256.85	669247.37	750.29	749.96
FTA-151-GP31(SS)	1170265.81	669260.40	750.15	NA
FTA-151-GP32(W)	1170238.98	669238.91	749.53	749.30
FTA-151-GP32(SS)	1170242.01	669236.74	749.47	NA
FTA-151-GP33(W)	1170240.07	669259.09	750.42	750.42
FTA-151-GP33(SS)	1170230.72	669258.15	750.05	NA
FTA-151-GP34	1170396.70	668980.98	745.60	748.11
FTA-151-GP35	1170369.27	668967.52	746.65	746.58
FTA-151-GP36	1170341.86	668994.04	748.88	752.46
FTA-151-GP37	1170322.53	668994.52	747.80	NA
FTA-151-GP38	1170103.79	669024.14	746.47	NA
FTA-151-GP39	1170062.87	669015.38	746.79	NA
FTA-151-GP40	1170026.03	669012.53	745.65	747.79
FTA-151-GP44	1170968.65	668227.45	732.12	736.39
FTA-151-GP45	1170981.71	668211.04	731.47	736.34
FTA-151-GP46	1170281.88	669636.05	750.58	751.92

Appendix E

Survey Data
GSA Warehouse Area
Parcels 151(7), 2(7), 3(7), 4(7), 67(7), 69(7), 91(7), 111(7), 128(7), 129(7), and 238(7)
Fort McClellan, Calhoun County, Alabama

Sample Location	Northing	Easting	Ground Elevation (ft msl)	Top of Casing Elevation (ft msl)
FTA-151-GP47	1170293.73	669647.41	750.38	752.62
FTA-151-GP48	1170315.73	669515.95	750.47	752.03
FTA-151-GP49	1170343.24	669529.87	750.50	752.58
FTA-151-GP50(W)	1170348.26	669554.99	749.93	753.09
FTA-151-GP50(SS)	1170389.83	669593.00	753.27	NA
FTA-151-GP51	1170198.48	669001.22	745.63	746.65
FTA-151-GP52(W)	1170210.05	668957.71	743.71	745.74
FTA-151-GP52(SS)	1170180.77	668950.24	745.84	NA
FTA-151-GP53	1170233.73	668966.88	744.41	744.73
FTA-151-GP54	1170550.53	670671.61	753.15	754.80
FTA-151-GP55	1170505.55	670687.33	751.18	752.93
FTA-151-GP56	1170518.60	670625.56	750.15	753.44
FTA-151-MW01	1170366.83	670165.38	749.91	749.69
FTA-151-MW02	1170373.05	670140.91	749.73	749.52
FTA-151-MW03	1170408.08	670020.25	748.05	747.59
FTA-151-MW04	1170437.09	670094.50	747.56	747.31
FTA-151-MW05	1170422.07	670163.26	749.10	749.32
FTA-151-MW06	1170409.96	670233.57	748.95	750.09
FTA-151-MW07	1170335.04	669006.22	749.29	749.18
FTA-151-SW/SD01	1171670.76	668269.26	724.19	NA
FTA-151-SW/SD02	1171399.70	668681.07	723.51	NA
FTA-151-SW/SD03	1171201.71	668966.04	729.94	NA
FTA-151-SW/SD04	1170957.93	669307.25	730.11	NA
FTA-151-SW/SD05	1170536.83	670476.20	742.78	NA
FTA-151-SW/SD06	1170392.67	668565.83	733.20	NA
FTA-151-SW/SD07	1171330.41	668042.35	724.12	NA
WS-151-SW/SD01	1169745.87	669101.71	739.31	NA
PPMP-60-SW/SD01	1171455.35	668050.96	719.94	NA
UST-3-GP01	1170526.15	668566.37	738.39	NA
UST-3-GP02	1170488.66	668545.63	737.51	NA
UST-3-GP03	1170505.49	668510.98	737.55	NA
UST-3-MW01	1170530.89	668571.80	739.08	738.86
UST-3-MW02	1170512.54	668532.46	737.38	737.17
UST-3-MW03	1170490.49	668522.09	737.71	737.54
UST-3-MW04	1170506.89	668507.79	737.40	737.19

Horizontal coordinates referenced to the U.S. State Plane Coordinate System, Alabama East Zone, North American Datum (NAD83), 1983.

Elevations referenced to the North American Vertical Datum of 1988 (NAVD88).

ft msl - Feet mean sea level.
NA - Not applicable, temporary well not installed.

Final

Site Investigation Report
GSA Warehouse Area
Parcels 151(7), 2(7), 3(7), 4(7), 67(7), 69(7), 91(7), 111(7), 128(7), 129(7), and 238(7)

Volume II of II
Appendices F-I

Fort McClellan
Calhoun County, Alabama

Prepared for:

U.S. Army Corps of Engineers, Mobile District
109 St. Joseph Street
Mobile, Alabama 36602

Prepared by:

IT Corporation
312 Directors Drive
Knoxville, Tennessee 37923

Task Order CK05
Contract No. DACA21-96-D-0018
IT Project No. 774645

December 2002

Revision 3